




UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, Ground Floor
Kolkata-700073
Website:-www.caluniv.ac.in

1st CORRIGENDUM of the N.I.Q No. Eng
/EQ- 293 /20-21 Dated: 26.02.2021

1	N.I.Q No	:	Eng/EQ-293/20-21	Dated-26/02/2021
2	Name of Work	:	Supply & Installation of Electrical Cubicle panel at 2 nd floor, Applied Physics Building, ,Raja bazar Science college, CU, Kolkata-9	

In reference to the above N.I.Q, Item Schedule should be considered as attached herewith in lieu of previous item schedule. Other terms and conditions will remain unchanged.


02/03/21

UNIVERSITY ENGINEER (C.U)

**ITEM SCHEDULE FOR THE ELECTRICAL WORK OF THE
INSTALLATION OF ELECTRICAL DISTRIBUTION PANEL AT 2ND
FLOOR APPLIED PHYSICS BUILDING , RAJABAZAR SCIENCE
COLLEGE, CU, KOLKATA-9.**

Schedule Followed PWD schedule 2017 & Present Local Market Price					
Item No	Description of Items	Unit	Rate	Qty	P
1	Supply, Installation and testing-commissioning of indoor type wall mounted sheet steel (14 SWG) Electrical cubicle panel shall be fabricated from CRCA sheet steel vermin proof suitable for 415Volt, 3 phase, 50Hz AC Supply which consist of 250A,25KA MCCB as incomer,100A FP MCCB, 25KA-4 Nos, 63A FP MCB-4 Nos, 40A FP MCB-4 nos and 32A DP MCB -6 nos as outgoing, 250A Cu Busbar ,ON/OFF indication Lamp for 3 Phase which is connected through the 2 Amp control fuse, Ammeter and voltmeter with selector switch and provide CT link and provide Incoming and outgoing stud type terminal with phase separator sheet. The panel board shall be painted with powder coated and light grey shade and there should be ventilation provision in the panel.	No		1	
2	Supplying and fixing compression type gland complete with brass gland, brass ring and rubber ring for dual and moisture proof entry of XLPE/ PVC armoured cables as below (Page no-F-4, Item no-7-c & d)				
	3.5 Core 95 sqmm cable	Each		1	
	4 Core 16 sqmm cable	Each		1	
3	Finishing the end of following PVC armoured cable by crimping method incl supplying and fixing solderless socket, tapes, antocorrosive paste and jointing materials				
	3.5 Core 95 sqmm cable	set		1	
	4 Core 16 sqmm cable	set		1	
4	Dismantle the existing electrical Main switch , Busbar and necessary cable	Lumsum			
5	Supplying and Drawing 1.1 KV single core stranded FR PVC insulated and unsheathed single core stranded copper wire (Brand approved by EIC) of the following sizes in the prelaid polythene pipe and making necessary connection as required-				
	4X6 sq mm	Mtr		150	
	3X10+1X6 sq mm	Mtr		125	


 2/3/24.
 UNIVERSITY ENGINEER (C.U)




UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER CORRIGENDUM

- | | |
|----------------------------|------------------|
| 1. N.I.T NO. Eng/287/20-21 | Date: 26.02.2021 |
| 2. N.I.T NO. Eng/288/20-21 | Date: 26.02.2021 |
| 3. N.I.T NO. Eng/289/20-21 | Date: 26.02.2021 |

In reference to the above N.I.T. Nos., the following the last Date of tender Submission should be considered as in lieu of previously mentioned date of submission and other terms and conditions will remain unchanged.

- | | |
|----------------------------|------------------|
| 1. N.I.T NO. Eng/287/20-21 | Date: 08.03.2021 |
| 2. N.I.T NO. Eng/288/20-21 | Date: 08.03.2021 |
| 3. N.I.T NO. Eng/289/20-21 | Date: 08.03.2021 |


2/3/21

UNIVERSITY ENGINEER (C.U)